


KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Northridge Oil, Inc.

Complete Address P.O. Box 18271, Denver, Colorado 80218

Lease Name Dresback Well No. 1-B

Location C NE SW Sec. 7 Twp. 21 Rge. 6 (E) (W) X

County Rice Total Depth 3528'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 5 PM Day 20 Month November Year 1972

The above well was plugged as follows:

Hole filled with sand to 3500' and cemented with 5 sacks cement.

Hole filled with mud to 215'. Rock bridge set from 215' to 200' and hole cemented

with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to

30' and hole cemented to base of cellar with 10 sacks cement.

(Casing parted at 600' and 600' was all that was recovered.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/22/72
INV. NO. 6660-U