

State of Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

15.159.00630.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1962

CONSERVATION DIVISION
Wichita, Kansas
7-2-62

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date June 26, 1962, authorized

The following plugging operation:

Operator's full Name: Lee Phillips Oil Company

Complete Address: 1407 Union Natl. Bank Bldg., Wichita, Kansas

Lease Name: Johnson Well No. 1

Location: NE SW SE Sec. 11 Twp. 21 Rge. 9 (E) (W)

County Rice Total Depth: 3395'

Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐

D & A ☒ Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 215' with
heavy mud. Push plug and $\frac{1}{4}$ sack hulls to 215' and cement with
20 sacks thru drill pipe. Fill hole to 35' with heavy mud.
push plug and $\frac{1}{4}$ sack hulls to 35' and cap with 10 sacks.
Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

