

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

15.159.19374.0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Paul G. BredehoftComplete Address 3415 Shannon Way, Wichita, Kansas 67206Lease Name Read Well No. 1Location NE SE NW Sec. 11 Twp. 21 Rge. 9 (E) (W) XCounty Rice Total Depth 3440'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Kelso Casing Pulling Co.Address Chase, Kansas License No. 683Operation Completed: Hour Noon Day 26 Month December Year 1973

The above well was plugged as follows:

Hole filled with sand to 2925' and cemented with 3 sacks cement. Gas broke in
after shooting off casing. Used 45 sacks weight mud, 50 sacks gel, and 50 sacks
cement to kill well. Squeezed hole with 3 sacks hulls, 20 sacks gel-mud, and 85
sacks cement pumped into 8-5/8" surface casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/9/74
INV. NO. 8378-W