

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20, 903 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Mega Petroleum Corp.

Complete Address 4925 GREENVILLE, SUITE 1180, DALLAS, TX 75206

Lease Name McElwain Well No. 1

Location SWNE Sec. 8 Twp. 28 Rge. 17 (East)(West)

County KIOWA Total Depth 4948'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co., Inc.

Address 200 Douglas Bldg., Wichita, KS 67202 License No. _____

Operation Completed: Hour: 9:30 AM Day: 9 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

- The 1ST Plug set @ 780' w/70 sz. 50/50 Pozmix, 4% gel-3% CC.
- The 2ND Plug set @ 450' w/40 sz Cmt.
- The 3RD Plug set @ 40'-0' as a solid bridge of 1/2 sz hulls, an 8 5/8" rubber & wood plug and topped w/10 sz Cmt.
- The 5TH Plug in the rat hole w/10 sz Cmt.
- The 6TH Plug in the water well w/5 sz Cmt.

Cementing by Halliburton

Amount of Surface Casing: 8 5/8" @ 455' w/300 sz. 60/40 Pozmix, 2% gel-3% CC.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Barluttan
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 9-27-82
INV. NO. 1232-W