

12-5

To: 070887
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-20,922.0000

C NW NE, SEC. 18, T 21 S, R 34 WXE

4620 feet from S section line

1980 feet from E section line

Lease Name Foster "B" Well # 1-18

County Finney 162.50

Well Total Depth 5000 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 316

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Operator: Lebsack Oil Production, Inc.

Name & Address P.O. Box 489

Hays, KS 67601

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 a.m. Day: 5 Month: 12 Year: 19 90

Plugging proposal received from C. Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 2832' w/80 sx cement, Perfs at 2650-58'

1st plug sand back to 2600' and dump 4 sx cement on top of sand through bailer,

2nd plug at 2000' with 50 sx cement, 3rd plug at 1100' with 80 sx cement,

4th plug at 350' with 50 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:50 p.m. Day: 5 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 2600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 50 sx cement through casing at 2000',

3rd plug at 1100' with 80 sx cement,

4th plug at 350' with 50 sx cement,

5th plug 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION DEC 10 1990 12-10-1990 CONSERVATION DIVISION Wichita, Kansas

INVOICED

observe this plugging.

DATE 1-7-96

Signed Dan Jordan (TECHNICIAN)

NO. 30366