

To: 1 090768
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 093-21,556.0000
180' S of
C SW NE, SEC. 8, T 21 S, R 35 WXX
3120 feet from S section line
1980 feet from E section line

12-20
TECHNICIAN'S PLUGGING REPORT
Operator License # 31514
Operator: Thoroughbred Associates, LLC
Name & Address: 10 Colonial Court
Wichita, KS 67207

Lease Name Williams Well # 1
County Kearny 163.41
Well Total Depth 5028 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 9 p.m. Day: 19 Month: 12 Year: 19 96

Plugging proposal received from Walter Brown
(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Base 2250'
1st plug at 2250' with 50 sx cement, 2nd plug at 1060' with 80 sx cement,
3rd plug at 440' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12 a.m. Day: 20 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,
2nd plug at 1060' with 80 sx cement,
3rd plug at 440' with 50 sx cement, 12-23-1996
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel ~~by~~ floseal by Allied.
(If additional description is necessary, use BACK of this form.)

1 (XXX) did not observe this plugging.

Signed _____
(TECHNICIAN)

INVOICED
DATE JAN 03 1997
INV. NO. 47252
12-20

MAR 14 1997

FOR KCC-USE:

15.093.21556.0000

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 12-10-96

State of Kansas

093-21,556

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date ... December ... 11 ... 1996 ... month ... day ... year

Spot 180 S OF East ... SW ... NE ... Sec ..8.. Twp .21S. S, Rg .35W. xx West

OPERATOR: License # ...31514... Name: Thoroughbred Associates, LLC... Address: 10 Colonial Court... City/State/Zip: Wichita, Kansas 67207... Contact Person: Robert C. Patton... Phone: (316) 685-1512

3120' feet from South/ North line of Section ... 1980' feet from East West line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Kearny... Lease Name: Williams... Well #: 1... Field Name:

CONTRACTOR: License #: 30684... Name: Abercrombie Drilling, Inc.

*Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Marmaton

Nearest lease or unit boundary: 660'

Ground Surface Elevation: Est. 3155 feet MSL

Water well within one-quarter mile: yes XX no

Public water supply well within one mile: yes XX no

Depth to bottom of fresh water: 180'

Depth to bottom of usable water: 1060'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 400'

Length of Conductor pipe required: N/A

Projected Total Depth: 5000'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations: well farm pond X other

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OAWO ... Disposal X Wildcat ... Cable ... Seismic; ... # of Holes ... Other

If OAWO: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes XX no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 6/5/97

Will Cores Be Taken? yes X no

If yes, proposed zone:

AFFIDAVIT

* PRORATED AND SPACED IN CHASE AND COUNCIL GROVE 200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Walter Brown SPUD DATE 12-10-96 INIT. SM LENGTH SURFACE PLANNED 400 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2" 4 1/2" CONDUCTOR ANHYDRITE T- B- 2250 ELEVATION TD 5028 FORMATION MISSISSIPPIAN IRAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2250 Ft. W/ 50 SX 1/2 Base Anyh. @ 1060 Ft. W/ 80 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 440 Ft. W/ 50 SX 40' Plug @ 410 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SM DATE 12-19-96 TYPE OF CEMENT 60/40 6 1/4 Hosenp STARTING TIME 9:00 (AM/PM) DATE 12-19-96 COMPLETION TIME 12:00 (AM/PM) DATE 12-20-96 CEMENT COMPANY Allied