

1 050617

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,205.0000

C SW SE , SEC. 36 , T 21 S, R 24 W/EX

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Goebel Well # 1

Operator: Energy Three, Inc.

County Hodgeman 153.73

Name & Address P. O. Box 1505

Well Total Depth 4730 (Mississippi) feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 557

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A x

Other well as hereinafter indicated _____

Plugging Contractor Big Three Drilling Co., Inc. License Number 5836

Address Box 52, Gorham, KS 67640

Company to plug at: Hour: 6:00 pm Day: 25 Month: August Year: 1985

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-637-5487

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Elevation 2421'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 600' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 8:45 pm Day: 25 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement, 2nd plug at 600' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1985

INV. NO. 9817

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1985

CONSERVATION DIVISION

Signed Richard W. Lacey
(TECHNICIAN)