

1 050861

Plg'd. 12-21-86

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,266-0000

C. NE SE, SEC. 7, T 21 S, R 25 W/E

1980 feet from S section line

660 feet from E section line

Lease Name O'Brien Well # 1-7

County Hodgeman 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 308

TECHNICIAN'S PLUGGING REPORT

Operator License # 9826

Operator: Scarth Oil & Gas Co.

Name & Address 901 S. Polk

Amarillo, TX 79101

\_\_\_\_\_

\_\_\_\_\_

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 4:30 p.m. Day: 20 Month: 12 Year: 19 86

Plugging proposal received from Joe Weber

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe. Elevation 2398' KB

Anhydrite 1600-38'

1st plug at 1638' with 50 sx cement, 2nd plug at 800' with 60 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

\_\_\_\_\_

\_\_\_\_\_

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:30 a.m. Day: 21 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1638' with 50 sx cement,

2nd plug at 800' with 60 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

\_\_\_\_\_

\_\_\_\_\_

STATE CORPORATION COMMISSION.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied.

DEC 24 1986

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

Observe this plugging.

DATE 1-2-87

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 15711  
12-21

FORM CP-2/3  
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 5 1986 month day year

API Number 15-083-21266-0000

OPERATOR: License # 9826 Name Scarth Oil & Gas Co. Address 901 S. Polk City/State/Zip Amarillo, TX 79101 Contact Person J. F. Howell III Phone (806) 373-6932

C NE SE Sec. 7 Twp. 21 S, Rg. 25 East 1980 Ft. from South Line of Section 660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422 Name Abercrombie Drilling, Inc. City/State Wichita, KS

Nearest lease or unit boundary line 660 feet County Hodgeman

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext. Air Rotary OWWO Expl X Wildcat Cable

Lease Name O'Brien Well # 1-7 Ground surface elevation 393 feet MSL

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Municipal well within 330 feet: yes no Depth to bottom of fresh water 75

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11-14-86 Signature of Operator or Agent

Depth to bottom of usable water 1750-750 Surface pipe by Alternate: 1 2 X

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 5-17-87 Approved By 11-17-86

Surface pipe planned to be set 300 Conductor pipe required

Projected Total Depth 4500 Formation Mississippian

SPUD probably 12-11-86

Surface pipe 300'

Signature of J.F. Howell, Geologist

Date 11-14-86 Title J. F. Howell, Geologist

C NE SE Sec. 7 Twp. 21 S, Rg. 25 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 0 - 40' feet depth with 10 2nd plug @ 300' feet depth with 50 3rd plug @ Base Anhydrite feet depth with 50 4th plug @ feet depth with 5th plug @ feet depth with (2) Rathole with 10 sxs

60-40 Poz. 6% Gel 60-40 Poz. 6% Gel 60-40 Poz. 6% Gel (b) Mousehole with 15 sxs

PUSHER Joe Weber TD 4550 FORMATION MUD SURFACE PIPE 8 5/8 @ 308 ANHYDRITE 1600-1638 ELEVATION 2378 AS 12-20-86 4:30 PM 12-21-86 3:30 AM

1st PLUG @ 11638 FT. WI 50 SX 2nd PLUG @ 800 FT. WI 60 SX 3rd PLUG @ 370 FT. WI 50 SX 4th PLUG @ 40 FT. WI 10 SX RAT HOLE CIRCULATED WI 15 SX MOUSE HOLE CIRCULATED WI SX WATER WELL PLUGGED WI SX

CEMENT COMPANY Allied 60/40/6% Poz 60/40/6% Poz TECHNICIAN Lacey

James Howell, Geologist, Scarth Oil & Gas Co., Esc. Chy. a SC.

STATE CORPORATION COMMISSION DEC 24 1986 CONSERVATION DIVISION Wichita, Kansas