

1120008

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 083-21,163-0000

C SW NE, SEC. 24, T 21S, R 24 W/E
N SE Corner of
3300 FEET FROM XXS SECTION LINE
W SE Corner of
1980 FEET FROM XXE SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 9861

LEASE NAME Goebel WELL # 1

OPERATOR: Cart Oil Company
NAME & 3002 South Hillside
ADDRESS Wichita, KS 67216

COUNTY Hodgeman

WELL TOTAL DEPTH 4550 147.88 FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 5/8 FEET 354

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A x

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Murfin Drilling Co. LICENSE NUMBER 6033

ADDRESS 617 Union Center Building, Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 2:00 pm DAY: 17 MONTH: September YEAR: 19 84

PLUGGING PROPOSAL RECIEVED FROM Marvin Julian

(COMPANY NAME) Murfin (PHONE) 316-267-3241

WERE: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1600' with 50 sx cement

2nd plug at 750' with 70 sx cement

3rd plug at 400' with 35 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10-sx cement

6th plug to circulate rat hole with 15 sx cement

PLUGGING PROPOSAL RECEIVED BY Don C. Uebel
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE x

OPERATIONS COMPLETED: HOUR: 4:45 pm DAY: 17 MONTH: September YEAR: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1600' with 50 sx cement, 2nd plug at 750' with 70 sx cement, 3rd plug at 400' with 35 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

REMARKS: Used 60/40 Pozmix 2% gel 3% cc by Buie

I (~~Dox~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Don C. Uebel SD
(TECHNICIAN)

INVOICED

DATE 10-8-84

INV. NO. 4126

9-17

oct 25 1984

FORM CP-2/3
REV. 6-83