

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20804-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 24-21S-42W  
1250 feet from S Section Line, 1250 feet from E Section Line  
Lease/Unit Name: KUHN Well Number: 1  
County: HAMILTON Total Vertical Depth: 2825 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 500 W. TEXAS, STE 1190  
MIDLAND, TX 79701

Surface Casing Size: 8.625 feet: 250 **\$91.81**

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2003 3:00 PM  
Plug Co. License No.: 5382 Plug Co. Name: CHEYENNE DRILLING, INC.  
Proposal Rcvd. from: PHIL LLOYD Company: CHEYENNE DRILLING, INC. Phone: (620) 277-2062

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1250' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. NO RAT HOLE OR MOUSE HOLE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 03/05/2003 5:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1250' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. NO RAT HOLE OR MOUSE HOLE.

RECEIVED  
MAR 14 2003  
KCC WICHITA


Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
MAR 11 2003  
KCC Dodge City

Signed



(TECHNICIAN)

INVOICED  
DATE 3-14-03  
WEL. NO. 2003061302

Form CP-43