

5 030473.

12-27

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 113-20,057-0000  
SE, SEC. 13, T 21 S, R 2 W/R  
1980 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Dyck Well # 1

Operator: Thornton E. Anderson  
Name & Address: 212 N. Market, #508  
Wichita, KS 67202

County McPherson 113.23

Well Total Depth 3484 feet

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 226

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: am Day: 23 Month: 12 Year: 19 88

Plugging proposal received from Vernon Dunce, Jr.

(company name) Kelso Casing Pulling (phone)

were: 5-1/2" @ 3483' with casing parted/collapsed @ approx 1350' - cap w/5 sx  
cement by bailer - recover available pipe - bridge hole @ 300' - fill to  
surface with redi mix slurry cement.

Plugging Proposal Received by WK (TECHNICIAN)

Plugging Operations attended by Agent?: All Part top None

Operations Completed: Hour: 16:00 Day: 27 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT Checked bridge in hole @ 1230' - capped with 5 sx cement

by bailer - shot pipe @ 1140' - recovered - bridged hole on top of mud @ 293' -  
filled hole to surface with redi mix slurry (5 yds).

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
JAN 04 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: McPherson Concrete Products (If additional description is necessary, use BACK of this form.) 1-4-1989

INVOICED

(if applicable) observe this plugging.

DATE 1-9-89

Signed [Signature] (TECHNICIAN) SC

INV. NO. 23539