

5 020335

APR 1 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,347.0000

SW NE, SEC. 07, T. 21 S, R. 06 ~~W~~ ~~XX~~

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9155

Lease Name Ramsey Well # 2-7

Operator: Twin Star Petroleum, Inc.

County RICE 119.52

Name & Address 5358 S. 125th East Ave., Ste A

Well Total Depth 3616 feet

Tulsa, Oklahoma 74146

Conductor Pipe: Size 8 5/8 feet 209'-175 sx

Surface Casing: Size _____ feet

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768 Great Bend, Kansas 67530

Company to plug at: Hour: 1:00 p.m. Day: 1 Month: April Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316 793-9711

work: Fill hole with sand to 3500' and cement with 5 sacks cement. (Fluid @ 400') Set rock bridge on fluid @ 400' to 350' and fill hole to base of cellar with 5 1/2 yards ready-mix concrete.

Plugging Proposal Received by Ralph Tittel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 p.m. Day: 1 Month: April Year: 19 87

ACTUAL PLUGGING REPORT Hole filled with sand to 3500' and cemented with 5 sacks cement.

Rock bridge set on fluid @ 400' to 350' and hole cemented to base of cellar with 5 1/2 yards ready-mix concrete.

2620' of 5 1/2" casing recovered.

Remarks: 5 1/2"=3616-75 sx Perfs 3550-80 Concrete Enterprises, Inc. #32919
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging STATE CORPORATION COMMISSION

DATE 4-6-87

4-6-87

Signed [Signature]
(TECHNICIAN)

INV. NO. 16487

4-1

CONSERVATION DIVISION
Wichita, Kansas

Concrete Enterprises, Inc.

No. 32919

Transit-Mixed Concrete

PLANT 316-662-1219

OFFICE 316-662-5735

P. O. BOX #1

HUTCHINSON, KANSAS 67504-0001

DATE APRIL 1

13650

SOLD TO <u>TWIN STAR PETRO</u>		TERMS
DELIVER TO <u>FLUM & HUNTER RD. CW-2N-1 1/2 E</u>		CASH <input type="checkbox"/>
MAILING ADDRESS <u>STERLING RD</u>		COD <input type="checkbox"/>
TRUCK NO. <u>4</u>	DRIVER <u>LEN</u>	CHARGE <input type="checkbox"/>
		TOTAL YARDS

QUANTITY	MATERIAL	CODE	PRICE	AMOUNT
<u>5/2</u>	<u>CU. YD. 3000# CONCRETE</u>			

EXTRA WATER ADDED _____ GALLONS	DELIVERY CHARGE
30 MIN. FREE UNLOADING TIME	WAITING AND/OR UNLOADING TIME
WAITING AND / OR UNLOADING TIME _____	SUB-TOTAL
	SALES TAX
	TOTAL ▶

RECEIPT AND RELEASE

This concrete designed in accordance to A.C.I. Standards. Any water added to this design will be at purchaser's risk.

RECEIVED THE ABOVE MATERIAL IN GOOD CONDITION.

SIGN HERE Mike Gomez

"CAUTION" SKIN AREAS THAT COME INTO CONTACT WITH PORTLAND CEMENT OR MIXTURES CONTAINING PORTLAND CEMENT, EITHER DIRECTLY OR THROUGH SATURATED CLOTHING, SHOULD BE PROMPTLY WASHED WITH WATER. FAILURE TO DO SO MAY CAUSE SKIN IRRITATION OR BURNS.

IF ANY PORTLAND CEMENT OR MIXTURES CONTAINING PORTLAND CEMENT GETS IN THE EYE, RINSE IMMEDIATELY AND REPEATEDLY WITH WATER AND GET PROMPT MEDICAL ATTENTION.

KEEP OUT OF REACH OF CHILDREN

DELIVERY COPY

UNION

10/10/01

10/10/01