

15.159.05475.0000

1-30

2-070349

111  
P

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-139-20,389.0000

SE NE, SECTION 17 TOWNSHIP 21 RANGE 7W

OPERATOR LICENSE # 8021

4290 FEET FROM S SECTION LINE  
1320 FEET FROM E SECTION LINE

OPERATOR Moss Petroleum Company  
NAME & RR #1, Box 47  
ADDRESS Clafin, KS 67524

LEASE NAME: Johnson #8 4  
COUNTY: Rice  
WELL TOTAL DEPTH: 3426' 111,34

CONDUCTOR PIPE: " @  
SURFACE CASING: 12" @ 169'  
12

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing  
ADDRESS: Box 347, Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 1:00 DAY: 30 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Vernon Dunce  
COMPANY NAME: Kelso Casing PHONE: \_\_\_\_\_

WERE: Sand to 3360' & 7 sx - 35 sx @ 1200' - 35 sx 700' -  
250' to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 5:30 DAY: 30 MONTH: 1 YEAR: 1991

ACTUAL PLUGGING REPORT:  
CP-1 shows 8-5/8" surface, 5-1/2" csg, but there is  
12" surface pipe! 7" csg - sanded bottom to 3360' and 7  
sx - shot 7" off at 1800' - pulled to 1200' - pumped 35  
sx - pulled to 700' - pumped 35 sx - pulled to 250' -  
pumped to surface.

FEB 13 1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

REMARKS: Allied #1195 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

Jack Luthi  
Jack Luthi (AGENT)

DATE 2-25-91

INV. NO. 30867

FORM CP-2/3  
REV. 3/90

rw