

1-8 RECEIVED  
KANSAS CORPORATION COMMISSION

2-060292

136  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

JAN 29 1992

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-159-20,453.0000

C S/2 SE NE, SECTION 17 TOWNSHIP 21 RANGE 7W

OPERATOR LICENSE # 8021

2970 FEET FROM S SECTION LINE  
330 FEET FROM E SECTION LINE

OPERATOR Moss Petroleum Company  
NAME & 970 San Jacinto Tower  
ADDRESS 2121 San Jacinto Street  
Dallas, Texas 75201

LEASE NAME: Johnson #4  
COUNTY: Rice  
WELL TOTAL DEPTH: 3410'

110.82

PIPE: 7" @ 3409'/100 sx

SURFACE CASING: 8-5/8" @ 172'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: P. O. Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: a.m. DAY: 8 MONTH: 1 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Manny  
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 3360' - cap w/7 sx cmt - shoot pipe - pull csq  
to 900' & 35 sx cmt - pull csq to 400' & 35 sx cmt -  
pull csq to 250' & circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 1:30p DAY: 8 MONTH: 1 YEAR: 1992

ACTUAL PLUGGING REPORT:

Sanded to 3360' - capped w/7 sx cmt - shot pipe -  
pulled csq to 900' - 35 sx cmt - pulled csq to 400' &  
35 sx cmt - pulled csq to 250' & circ 120 sx cmt to  
surface - open hole - recovered 1529' of 7".

REMARKS: Allied Cem #2644 60/40 poz 6% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

R. Phil Worley  
R. Phil Worley (AGENT)

DATE 2-12-92

INV. NO. 34523