

5070022

D-14945

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SE NE NE, SEC. 17, T. 21 S, R. 7 @1E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8021

Lease Name JOHNSON Well # 3

Operator: MOSS PETROLEUM CO.

County RICE 110.27

Name & Address 3760 INTERFIRST TWO

Well Total Depth 3393 feet

DALLAS, TX 75270

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 112 ^{135SK}

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated 7" @ 3381 75SK NO CASING RECOVERY

Plugging Contractor ALLIED CEMENTING CO. License Number _____

Address GREAT BEARD, KS

Company to plug at: Hour: 10:00 Day: 15 Month: APRIL Year: 1986

Plugging proposal received from DON BRUNING

(company name) BRUNING DITCHING SERVICE (phone) _____

were: _____

Plugging Proposal Received by DAVID WERTZ
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:30 PM Day: 15 Month: APRIL Year: 1986

ACTUAL PLUGGING REPORT PUMPED 20SK GEL + 150SK 60/40 P02 w/6% GEL

INTO 7" CASING ON VACUUM, CLOSED IN FOR 3 HOURS. PUMPED 50SK 60/40 P02 6%

OPEN END INTO 7" FILLED 7" MAX PRESSURE 400 PSIG CLOSE IN O. RUN 1"

TO 150' CIRCULATE OUT w/50SK 60/40 P02 6% GEL.

Remarks: ALLIED # 1550

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

GIO TOMAN

APR 25 1986

APR 24 1986

signed David Wertz
(TECHNICIAN)

DATE

INV. NO. 13545

4-15

CONSERVATION DIVISION
Wichita, Kansas