

6-12

2-070462

106  
R

RECEIVED  
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

JUL 1 1992

API NUMBER: 15-159-20,435-0000 CONSERVATION DIVISION  
WICHITA, KS

C SE SE, SECTION 17 TOWNSHIP 21 RANGE 7W

OPERATOR LICENSE # 5142

660 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

OPERATOR Sterling Drilling Company  
NAME & P. O. Box 129  
ADDRESS Sterling, KS 67579

LEASE NAME: Johnson # JE-3  
COUNTY: Rice  
WELL TOTAL DEPTH: 2932' 95.29

CONDUCTOR PIPE: \_\_\_\_\_  
SURFACE CASING: 8-5/8" @ 179'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing  
ADDRESS: Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 11 MONTH: 6 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Darrell Kelso  
COMPANY NAME: Kelso Casing PHONE: \_\_\_\_\_

WERE: Sand to 2825' & 5 sx - 35 sx @ 925' - 35 sx @ 625' -  
300' to surface.

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 12:00 DAY: 12 MONTH: 6 YEAR: 1992

ACTUAL PLUGGING REPORT:

Could not get sand to bottom - went in w/line bridge  
@ 1131' - pulled csg - ran tub in - could not get back  
inside csg - pumped 150 sx cmt, 500# hulls there -  
pulled to 625' & pumped 35 sx - pulled to 300' & tried  
to circ to surf - couldn't - SDFN - in a.m. cmt was at  
500' - pumped 200 sx - got circ - pulled tub - cmt was  
still falling a little - topped back to surface.

REMARKS: Halliburton

I DID OBSERVE THIS PLUGGING.

INVOICED

15/

DATE 7-8-92

Jack Luthi (AGENT)

INV. NO. 35639

FORM CP-2/3  
REV. 3/90