

1040942

3-10

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,339 - 0000
80' S & 80' W
of C SE, SEC. 7, T 28 S, R 17 W/EX
1240 feet from S section line
1400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926
Operator: Advantage Resources, Inc.
Name & Address: 1775 Sherman St., Ste. 1375
Denver, CO 80203-4316

Lease Name Keller-Bates Well # 1
County Kiowa
Well Total Depth 4858 157.89 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 512

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:45 a.m. Day: 10 Month: 3 Year: 19 95

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

- were: 4 1/2" at 4858' w/250 sx cement, PBTD 4840', Perfs at 4757-74'
- 1st plug pump down 4 1/2" casing with 2 sx hulls and 20 sx cement,
- 2nd plug at 1060' with 50 sx cement
- 3rd plug at 540' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 10 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 20 sx cement,
2nd plug loaded hole with drilling mud and spotted through 4 1/2" casing at 1040' with 50 sx cement,
3rd plug at 540' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3060' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form)

I (did not) observe this plugging.

INVOICED
DATE MAR 29 1995
INV. NO. 42476

Signed [Signature] (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED 3-17-95
MAR 17 1995
WICHITA, KANSAS