

4-13-88

101R

1 061092

API NUMBER 15-097-21,048-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW NW, SEC. 13, T 28 S, R 17 W/EX  
4950 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3597

Operator: Servco Production/was Robert Gay  
Name & Address P.O. Box 266 Energy  
Plains, KS 67869

Lease Name Bevans Well # 1  
County Kiowa 162.40  
Well Total Depth 4997 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 13 Month: 4 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4992' Perfs at 4770-4801'

1st plug sand back to 4620' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release wiper plug and pump 130 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 13 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4620' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released wiper plug and pumped 130 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1937' of 5 1/2" casing.  
(if additional description is necessary, use BACK of \_\_\_\_\_)

observe this plugging.

DATE 4-26-88

INV. NO. 20467

Signed Paul A. Little (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

APR 19 1988 4-19-88

CONSERVATION DIVISION Wichita, Kansas