

4-13-88

100 R

To: 1 061093
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,060 -0000
NE NW, SEC. 13, T 28 S, R 17 W/E
4620 feet from S section line
3300 feet from E section line
Loose Name Bevans Well # 2

TECHNICIAN'S PLUGGING REPORT
Operator License # 3597

Operator: Servco Production/was Robert Gay
Name & Energy
Address Box 266
Plains, KS 67869

County Kiowa 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size feet
Surface Casing: Size feet

Abandoned Oil Well Gas Well Input Well SHD Well O&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 13 Month: 4 Year: 19 88

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711
were: 5 1/2" at 4500'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper
plug and pump 130 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a. Day: 13 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
wiper plug and pumped 120 sx cement.

Maximum pressure 800 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION 4-19-88

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Approved 2100' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(copy) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas
Signed Paul A. Luther (TECHNICIAN)

DATE 4-26-88

INV. NO. 20468