


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 11 Twp. 21S Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE
Lease Owner Lee Phillips Oil Co. E. H. Adair Oil Co.
Lease Name Johnson Well No. 1
Office Address 1005 E. Second, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 6-26-62 19
Application for plugging filed 6-26-62 19
Application for plugging approved 6-26-62 19
Plugging commenced 6-26-62 19
Plugging completed 6-26-62 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3395 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 215', plug, hulls and 20 sax cement.

Mud to 35', plug, hulls and 10 sax cement.

2 sax cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1962

CONSERVATION DIVISION
Wichita, Kansas

7-2-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. H. Adair Oil Co.
Address 1005 E. Second, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, K. W. Johnson, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. W. Johnson
Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 62

My commission expires 9-15-65 Notary Public.

E. H. Adair Oil Company
1005 East Second Street
Wichita 14, Kansas.

Lee Phillips Oil Company, and
E. H. Adair Oil Company
Johnson No. 1
NE SW SE of
Sec. 11-Twp. 21 South, Range 9 West,
Rice County, Kansas.

Elevation: 1,663 K.B.

Comm.: 6-18-62
Comp.: 6-26-62
Contractor:
E. H. Adair
8-5/8 in. s/csg.
@ 225 ft. w/175 sax.
Prop. D. & A.

Figures indicate bottoms of formations:

Lime and shale to	375	Lime to	2902
Shale and shells	570	Shale	2925
Salt and shale	1130	Lime	3241
Anhydrite	1180	Conglomerate	3348
Lime	1640	Lime	3380
Lime and shale	2700	Shale	3387
Lime	2760	Sand	3390
Black shale	2765	Shale	3395
Lime	2795	R.T.D.	3395
Shale	2894		

Tops:

HEEBNER	2760 (-1097)
DOUGLAS	2795 (-1132)
BROWN LIME	2894 (-1231)
LANSING-KANSAS CITY	2925 (-1262)
CONGLOMERATE	3241 (-1578)
VIOLEA	3348 (-1685)
SIMPSON SHALE	3380 (-1717)
SIMPSON SAND	3387 (-1724)

Certified correct:

K. W. Johnson
K. W. Johnson - Geologist.

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1962

CONSERVATION DIVISION
Wichita, Kansas