

RECEIVED
STATE CORPORATION COMMISSION


MAR 13 1975

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County. Sec. 11 Twp. 21 Rge. 9 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NE NW NE
Lease Owner I. O. Miller
Lease Name Stewart #2 Well No.
Office Address Ellis, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/27/74 19
Plugging completed 1/9/75 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	201	none
				4 1/2"	2997	880'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 2925', ran 3 sacks cement. Pulled pipe into, pulled 27 joints. Plugged well with 3 sacks hulls, 20 sacks gel and 85 sacks cement, 2% gel.
PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1975

My commission expires
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1974
CONSERVATION DIVISION
Wichita, Kansas

STEWART #2
NE NW NE SECTION 11-21S-9W
RICE COUNTY, KANSAS

COMMENCED: JUNE 9, 1965
COMPLETED: JUNE 13, 1965

OPERATOR - I. O. MILLER

DEPTH	FORMATION	REMARKS
FROM To		
0 75	CLAY AND SAND	
75 110	RED BED	
110 201	RED BED AND SHALE	RAN 10 JOINTS 8-5/8" CASING, SET @ 201 FT. WITH 210 BAGS CEMENT.
201 300	RED BED	
300 1080	SHALE AND SHELLS	
1080 1410	LIME AND SHALE	
1410 1990	LIME	
1990 2410	SHALE AND LIME	
2410 2790	LIME	
2790 2807	SHALE AND LIME	
2807 3000	LIME	
3000 TO		RAN 92 JOINTS 4 1/2" CASING, SET @ 2997 FT. WITH 75 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NE NW NE SECTION 11-21S-9W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 15TH DAY OF JUNE, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.