

15.159.30199.0000

WELL PLUGGING RECORD

RICE County. Sec. 11 Twp. 21S Rge. (E) 9 (W)

Location as "NE/CNW/SE" or footage from lines SW NE NE

Lease Owner I. O. MILLER

Lease Name STEWART Well No. 3

Office Address 619 BROWN BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed DEC. 1, 1965

Application for plugging filed (PHONE 12-1-65) DEC. 6, 1965

Application for plugging approved DEC. 1, 1965

Plugging commenced DEC. 1, 1965

Plugging completed DEC. 1, 1965

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN

Producing formation Depth to top Bottom Total Depth of Well 2965 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	208	8-5/8	208	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 200 FEET. SET FIRST PLUG @ 200 FEET WITH $\frac{1}{4}$ SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG WITH $\frac{1}{4}$ SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE @ 12:00 NOON.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1965
12-7-1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.

Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 6TH day of DECEMBER, 1965

Barbara J. Layton
BARBARA J. LAYTON Notary Public.

My commission expires FEB. 1, 1968



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

STEWART #3
 SW NE NE SECTION 11-21S-9W
 RICE COUNTY, KANSAS

COMMENCED: NOVEMBER 26, 1965
 COMPLETED: DECEMBER 1, 1965

OPERATOR - I. O. MILLER

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	SAND	
70	208	RED BED	RAN 10 JOINTS 8-5/8" CASING, SET @ 208' w/200 SACKS CEMENT.
208	253	SHALE	
253	264	ANHYDRITE	
264	1395	SHALE AND SHELLS	
1395	1595	LIME AND SHALE	
1595	1815	LIME	
1815	2595	LIME AND SHALE	
2595	2965	LIME	
2965	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SW NE NE SECTION 11-21S-9W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 6TH DAY OF DECEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.

RECORDED
 DEC - 7 1965
 COMMISSION EXPIRES FEBRUARY 1, 1968