

15.159.20807.0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rice SEC. 11 TWP. 21s RGE. 9w E/W
 Location as in quarters or footage from lines:
NW SE SW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Lebsack Oil Production, Inc.
 Lease Name Gullick #1-11 Well No. _____
 Office Address P.O. Box 389, Hays, Kansas 67601
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 7/13/83
 Plugging completed 7/20/83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3025'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 212' | none |
| | | | | 4 1/2" | 3024' | 2524' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 2900' & 4 sacks cement. Shot casing at 2524'. Pulled 60 joints of pipe. Plugged well with 5 hulls, 20 gel, 8 5/8 plug & 100 sacks 50/50 poz 2% gel.

Plugging complete

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 83

My Commission expires:  Irene Hoover
 Notary Public.
 STATE CORPORATION COMMISSION

JUL 25 1983

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG

GULLECK #1-11

Located: NW SE SW, Section 11-21S-9W, Rice County,
Kansas.

OWNER: Lebsack Oil Production, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 24, 1979
COMPLETED: March 2, 1979

TOTAL DEPTH: 3025'

LOG

CASING RECORD

| | | |
|-------------|-------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 0 - 155 | Sand and Shale, Red Bed | Ran 5 joints 8 5/8" casing, 200.66' |
| 155 - 215 | Red Bed - Shale | set at 212' K.B. with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 6:30 PM, 2-24-79, by Howco. |
| 215 - 1415 | Shale | |
| 1415 - 2395 | Lime and Shale | |
| 2395 - 2755 | Lime | |
| 2755 - 2910 | Lime and Shale | |
| 2910 - 3025 | Lime | Ran 72 joints 4 1/2" OD, 10.5# casing, 3029' cemented at 3024' K.B. with 100 sacks 18% salt 50/50 Pozmix with 2% gel and 3/4 of 1% CFR-2. Plug down at 4:00 AM, 3-2-79, by Howco. |

Ref - 2950-54

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1983

CONSERVATION DIVISION
Wichita, Kansas