


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County. Sec. 27 Twp. 28S Rge. 16WE/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C SE NE  
Lease Owner Imperial Oil Company  
Lease Name Scott Well No. 1-27  
Office Address 720 Fourth Financial Ctr., Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed Oct. 15 1978  
Application for plugging filed (verbally) Oct. 15 1978  
Application for plugging approved (verbally) Oct. 15 1978  
Plugging commenced Oct. 15 1978  
Plugging completed Oct. 15 1978  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bil Owens  
Producing formation Depth to top Bottom Total Depth of Well 4838'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Set 1st plug at 500' with 50 sacks  
2nd plug at 40' with  $\frac{1}{2}$  sack of hulls and 12 sacks cement  
rathole with 3 sacks.  
Plug was down at 1:00 p.m. on October 15, 1978.  
Cemented with 50-50 posmix, 6% gel.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1978

10-19-1978  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1978

Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires August 21, 1982



CONTRACTOR'S WELL LOG

OPERATOR: Imperial Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: SCOTT #1-27  
 LOCATION: C SE NE, Section 27-28S-16W  
 Kiowa County, Kansas  
 SPUD DATE: October 7, 1978  
 COMPLETION DATE: October 15, 1978

0	278	Sand
278	1195	Red bed & Shale
1195	2143	Shale & Lime
2143	3235	Lime & Shale
3235	3440	Shale & Lime
3440	3619	Lime & Shale
3619	4095	Shale & Lime
4095	4477	Lime & Shale
4477	4544	Shale & Lime
4544	4738	Lime & Shale
4738	4790	Lime, Shale & Chert
4790	4838	Shale & Lime
	4838	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 19 1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

Spud hole at 9:15 a.m., October 7, 1978. Drilled 447' of 12 1/4" hole. Ran 11 joints of new 8 5/8" - 20# surface casing. Set at 447' with 175 sacks of Halliburton lite, 3% Ca.Cl., followed with 125 sacks of common cement, 3% Ca.Cl. Cement did circulate. Plug was down at 3:15 p.m., October 7, 1978.

T.D. 4838'. Set 1st plug at 500' with 50 sacks, 2nd plug at 40' with 1/2 sack of hulls and 12 sacks cement, rathole with 3 sacks. Plug was down at 1:00 p.m. on October 15, 1978. Cemented with 50-50 posmix, 6% gel.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Scott #1-27, C SE NE, Section 27-28S-16W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 18th day of October, 1978.



Sherrie L. Brooks  
 Sherrie L. Brooks, Notary Public

My commission expires August 21, 1982.