


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 12 Twp 28S Rge 17 (W)
Location as "NE/CNW/SWK" or footage from lines SE SE SE
Lease Owner K & E Drilling, Inc.
Lease Name Kemp Well No. #1
Office Address 1006 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 1, 1955
Application for plugging filed November 1, 1955
Application for plugging approved November 1, 1955
Plugging commenced November 1, 1955
Plugging completed November 1, 1955
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5063 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	422	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 5066' to 422'
Set wooden plug with 20 sacks cement. Second plug at 35'
and capped with 10 sacks cement.

11-5-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1955

My commission expires June 25, 1956
Francis Mader Notary Public.

PLUGGING
FILE SEC 12 T 28 R 17 W
BOOK PAGE 13 LINE 19

K & E DRILLING, INC.

SE SE SE 12-28S-17W
Kiowa County, Kansas

Kemp #1

Comm: 10-12-55
Comp: 11-1-55
Total Depth: 5066'

Casing 8 5/8" set @ 422'
Cement 300 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Clay	0 - 30
Sand & shale	30 - 270
Blue shale	270 - 325
Sand	325 - 360
Red rock	360 - 380
Sand	380 - 422
Red Bed	422 - 705
Sand & red bed	705 - 945
Red rock	945 - 1085
Anhydrite Lime	1085 - 1140
Blue, shale, red rock & lime shells	1140 - 1645
Shale & shells	1645 - 2185
Lime	2185 - 2690
Lime & shale	2690 - 2705
Lime	2705 - 2970
Lime & shale	2970 - 3420
Lime	3420 - 3705
Lime & shale	3705 - 3775
Lime	3775 - 3885
Lime & shale	3885 - 3940
Lime	3940 - 4032
Lime & shale	4032 - 4199
K.C.Lime	4199 - 4215
Lime	4215 - 4638
Lime & shale	4638 - 4724
Mississippi Chert	4725 - 4737
Chert & shale	4737 - 4739
Chert	4739 - 4740
Coring Chert	4740 - 4767
Shale lime	4767 - 4795
Viola Chert	4795 - 4815
Chert & shale	4815 - 4854
Viola Chert	4854 - 4918
Lime	4918 - 4980
Simpson shale & sand	4980 - 5025
Shale & Lime	5025 - 5042
Arbuckle Lime	5042 - 5063

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

11/3/55
1657-13-115
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

Walt Smith

Subscribed and sworn to before me this 3rd day of November, 1955.

Francis Mullen
Notary Public

My commission expires: June 25, 1956

PLUGGING
FILE SEC-12728 R-17W
BOOK PAGE 13 LINE 17