

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,286-0000

LEASE NAME Bevans "B"

WELL NUMBER 2

4140 Ft. from S Section Line

2570 Ft. from E Section Line

SEC. 13 TWP. 28 SRGE. 17 (XXX)(W)

COUNTY Kiowa

Date Well Completed 01-23-90

Plugging Commenced 01-23-90

Plugging Completed 01-23-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Eric Waddell Company

ADDRESS Box 349, Natoma, KS 67651

PHONE#(913) 885-4497 OPERATORS LICENSE NO. 6725

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-23-90 (date)

by State Plugger, Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4816'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	363.17'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Circulate heavy mud in hole. 1st plug from 1125' to 925' w/50 sx. 2nd plug from 560' to 400' w/40 sx. 3rd plug from 380' to 220' w/40 sx. 4th plug from 40' to surface w/10 sx. Rathole-15 sx. Mousehole-10 sx. Water Well-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eric Waddell Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
150 N. Main, Suite 801
(Address) Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1990
SUBSCRIBED AND SWORN TO before me this 8th day of February, 19 90

CONSERVATION DIVISION
Wichita, Kansas
My Commission Expires: May 18, 1993
Sharan J. Branstetter Notary Public

