

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rush County, Sec. 28 Twp. 18 Rge. (E) 16 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$

Lease Owner Solar Oil Company

Lease Name Wagner Well No. 1

Office Address 1117 Union National Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-25- 19 58

Application for plugging filed 2-25- 19 58

Application for plugging approved 2-25- 19 58


Plugging commenced 2-26- 19 58

Plugging completed 2-26- 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3693 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1120'	0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud went  $\frac{1}{2}$  way in hole layed down drill pipe run other  $\frac{1}{2}$  in and layed down, filled hole with heavy mud to 300'. Set plug at 300' and cemented thru 10 joints of drill pipe with 20 sacks cement. Filled hole to 35' with heavy mud, set plug at 35' and cemented with 10 sacks cement to bottom of cellar.

STATE OF KANSAS  
CORPORATION COMMISSION

MAR 11 1958 3-11-1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 915 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

William J. Duckett (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William J. Duckett

915 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 58

A. R. Derrington  
(A. R. Derrington) Notary Public.

My commission expires 8-20-60

PLUGGING  
FIL SEC. 28 T. 18 R. 16  
BOOK PAGE 87 LINE 39

# WELL LOG

15-165-01808-0000

COMPANY Solar Oil Company

SEC. 28 T. 18 R. 16W  
LOC. SW 1/4 NW 1/4 SW 1/4

FARM Wagner

NO. 1

TOTAL DEPTH 3693'

COMM. 2-14-58

COMP. 2-26-58


COUNTY Rush

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



ELEVATION 2066 K.B.

PRODUCTION

### CASING

20	10
15	3/8 8 5/8" - 1120'
12	6
13	5

FIGURES INDICATE BOTTOM OF FORMATIONS

0-270	Post Rock & Shale
270-500	Shale
500-650	Sand Shale & Shells
650-860	Red Bed
860-1106	Red Bed & Sand
1106-1145	Anhydrite
1145-1550	Red Bed & Shale
1550-1800	Shale & Shells
1800-1980	Shale & Shells w/Lime Streaks
1980-2210	Shale & Shells
2210-2450	Shale & Lime
2450-2615	Shale & Shells
2615-2710	Lime & Shale
2710-3025	Shale & Shells
3025-3405	Lime & Shale
3405-3505	Lime
3505-3681	Lime & Shale
3681-3691	Sand
3691-3693	Granite Wash
3693	Total Depth

### Geologic Tops

Anhydrite	1106
Hoebner	3318
Lansing KC	3377
Reagan Sand	3682
Granite Wash	3690

RECORDED  
STATE CORPORATION COMMISSION

MAR 11 1958

COMMISSION

PLUGGING  
 H. SEC 28 T. 18 R. 16W  
 BOOK PAGE 87 LINE 39

State of KANSAS }  
 County of SEDGWICK } SS:

I, William J. Duckett of the Lewis Drilling Company  
 upon oath state that the above and foregoing is a true and correct copy of the log of the Wagner #1 well.

William J. Duckett

Subscribed and sworn to before me this 5th day of March 19 58

My Commission Expires: 8-20-60

A. R. Derrington  
 A. R. Derrington NOTARY PUBLIC