

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County, Sec. 2 Twp. 21 Rge. 9 EXW
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

NW/SE/SE (approx.)
Lease Owner R. E. Davis

Lease Name Schafer Well No. 1

Office Address Box 108, Great Bend, KS 67530

Character of Well (Completed as Oil, Gas or Dry Hole) _____
Oil

Date Well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced July 6 1979

Plugging completed July 12 1979

Reason for abandonment of well or producing formation _____
Depleted


If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3450'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUF IN	PULLED OUT
				8 5/8	253'	NONE
				4 1/2"	3093'	500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Shot casing at 440'

Pulled 500' of 4 1/2" casing

Squeezed well with one (1) sack hulls, 20 sacks gel, one (1) sack hulls,

85 sacks 50/50 pox mix with 2% added gel

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1979

7-24-1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold

James W. Rockhold Box 698, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1979

STATE NOTARY PUBLIC
KANSAS
CATHY L. COLE
Barton County, Kansas
My Appt. Expires 12/31/1982

Cathy L. Cole
Notary Public.

My commission expires _____

DRILLER'S WELL LOG

15.159.20667.0000

DATE COMMENCED: 1-12-77
 DATE COMPLETED: 1-18-77

Allen Drilling Company
 Don Schafer #1
 S $\frac{1}{2}$ SE $\frac{1}{4}$ Sec. 2-21-9W
 Rice County, Kansas

ELEVATION: 1676 K.B.
 1670 G.L.

0- 80' Sand
 80- 165' Red Bed & Shale
 165-1220' Shale
 1220-1240' Shale & Lime
 (Not Called) Anhydrite
 1240-1299' Lime
 1299-1366' Lime
 1366-1984' Lime
 1984-2138' Lime
 2138-2365' Lime
 2365-2427' Lime
 2427-2470' Shale & Sand
 2470-2762' Lime
 2762-2896' Shale
 2896-2925' Lime & Shale
 2925-3272' Lime
 3272-3315' Shale
 3315-3350' Chert
 3350-3422' Sand
 3422-3450' Dolomite
 3450' RTD

FORMATION DATA
 (Per Electric Log)

Anhydrite	(Not Called)
Herington	1240
Winfield	1299
Towanda	1366
Brownville	1984
Tarkio	2138
Howard	2365
Severy	2427
Topeka	2470
Heebner	2762
Brown	2896
Lansing	2925
Maquoketa	3272
Viola	3315
Simpson	3350
Arbuckle	3422
RTD	3450

SURFACE PIPE:

Set 252 ft of 8 5/8", #28 used pipe w/200 sacks common, 2% gel 3% cc.

PRODUCTION PIPE:

Ran new 4 $\frac{1}{2}$ " 10.5# casing. Set @ 3094' w/400 sacks 50/50 Pozmix, 4% gel, followed w/100 sacks 50/50 Pozmix 2% gel w/18% salt.

Plug down @ 2:50 P.M. by Sun Cementing.

RECEIVED
 CORPORATION CO. MISSION

A F F I D A V I T

APR 30 1979

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

CONSERVATION DIVISION
 Wichita, Kansas

Glenn J. Bishop, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Earl Allen