


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County, Sec. 2 Twp. 21 Rge. 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner Great Bend Pipe & Supply
Lease Name Schafer Well No. C#3
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/30/67 19
Plugging completed 11/ 4/67 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 2956 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	234'	none
				5-1/2"	2946'	2494'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded back to 2925' and ran 5 sacks of cement.
Loaded hole. Shot pipe at 2482', spotted oil, pumped 45 barrels oil, chased oil with plug with 60 barrels water. Worked pipe loose.
Pulled 5 1/2" casing. Tried to bail hole, couldn't. Pushed plug to 230', sanded and mud, tried to bail again and couldn't. Set 15 sacks of cement. Let set over night. Bailed hole dry, dumped 5 sacks of cement, mudded hole to 30' and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
NOV 18 1967
CONSERVATION DIVISION
WICHITA, KANSAS
11-13-1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY, INC.
Address CHASE, KANSAS 67524

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 67

My commission expires February 15, 1971
Margaret Melcher Notary Public.

15.159.30182.0000

WELL LOG

RECEIVED
OCT 20 1965

LEE PHILLIPS OIL COMPANY
SCHAFFER "C" #3, SE SW SE
Section 2-21S-9W
Rice County, Kansas

CONSERVATION DIVISION
Wichita, Kansas

ELEVATION: 1675' KB

ROTARY COMMENCED: 10-9-65
ROTARY COMPLETED: 10-15-65

Figures indicate bottom of formation:

PIPE RECORD:
8 5/8" set at 234'
with 185 sacks cement.
5 1/2" set at 2946'
with 75 sacks cement.

0	to	10	cellar
		20	clay
		65	sand
		233	shale & shells
		268	red rock
		1445	shale & shells
		1840	lime & shale
		2360	shale & shells
		2956	lime & shale
		2956	rotary total depth

TOPS:
Heebner 2757
Toronto 2779
Douglas 2794
Brown Line 2895

STATE OF KANSAS)
COUNTY OF BARTON) SS

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells
Dean Wells, Partner

Subscribed and sworn to before me on this 18th day of October, 1965.

George A. Meyer
George A. Meyer, Notary Public

My commission expires: February 10, 1967.