

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.12905.0000

LEASE NAME Rose #5

WELL NUMBER _____

SPOT LOCATION SW NW SE

SEC. 22 TWP. 21 S RGE. 12 W (E) of (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 9/6/84

Plugging Completed 9/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS P.O. Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3583'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	282'	none
				5 1/2"	3581'	1797'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3370' & 5 sacks cement. Shot pipe at 2709', 2512', 2301', 2027', & 1797'. Pulled total of 58 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks cement 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 20th day of Sept., 1984



Irene Hoover
Notary Public

My Commission expires: _____

15.185.12905.0000

ROSE # 5 - SW NW SE/4 Section 22-21-12 Stafford County, Kansas
Company - S. A. Murphy
Contractor - Virginia Drilling Co., Inc.
Commenced - April 6, 1953
Completed - April 17, 1953
Elevation - 1852 RB
Total Depth - 3583

8 5/8" set at 282
5 1/2" set at 3581

FORMATION	DEPTH
Sand-shale	0- 282
Red Bed	282- 370
Shale-sand	370- 880
Shale-shells	880-1540
Lime	1540-2035
Lime brk.	2035-2165
Shale-lime	2165-3040
Lime brk.	3040-3048
Lime	3048-3170
Lime-shale	3170-3240
Shale	3240-3251
Lime	3251-3410
Lime-shale	3410-3565
Lime	3565-3583 T D

TOPS:

- 3114 - Heebner
- B 3251-Brown lime
- 3264 - Lansing KC
- 3503 - Cherty Cong.
- 3535 - Simpson shale
- 3580 - Arbuckle

C. Tools - Dr. to 3630 1/2

S. A. Murphy

S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this
21st day of April, 1953.

Charles J. ...

Notary Public

My commission expires: Feb. 5, 1957.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1984

CONSERVATION DIVISION
Wichita, Kansas