

15.185.19541.0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 22 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE  
Lease Owner S. A. Murphy  
Lease Name Rose Well No. 4  
Office Address 701 Brown Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-20-53 19  
Application for plugging filed 3-19-53 19  
Application for plugging approved 3-19-53 19  
Plugging commenced 3-20-53 19  
Plugging completed 3-20-53 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives,  
Producing formation Depth to top Bottom Total Depth of Well 3691 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	280	8 5/8"	283	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 270 ft - set plug w/ 20 sx cement  
Mudded to 35 ft - set plug w/ 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
MARCH 24 1953  
3-24-1953  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Virginia Drlg Co Inc.  
Address 701 Brown Bldg. Wichita 2, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
S. A. Murphy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Murphy  
701 Brown Bldg. Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March 1953

Notary Public

My commission expires Feb. 5, 1957

PLUGGING  
FILE SEC 22 T 21 R 12  
BOOK PAGE 26 LINE 25

Rose # 4 - SW SW SE Section 22-21-12 Stafford County, Kansas.

Company - S. A. Murphy

Contractor - Virginia Drlg Co Inc

Commenced - Feb. 14, 1953

Completed March 20, 1953

Elevation - 2843 DF

Total Depth - 3691

8. 5/8" set at 280 ft.

FORMATION	DEPTH
Sand	0- 70
Sand - shale	70- 280
Shale - shells	280- 735
Shale - lime	735-1156
Salt - shale	1156-1325
Shale - lime	1325-1555
Brkn lime	1555-1690
Lime	1690-1810
Lime - shale brk	1810-1895
Lime	1895-1965
Brkn lime	1965-2025
Lime	2025-2125
Lime brk	2125-2250
Shale - shells	2250-2475
Shale - lime shells	2475-2625
Lime brk	2625- <del>2680</del> 2735
Lime - shale	<del>2680</del> 2735-2870
Lime	2870-3200
Lime - shale	3200-3265
Lime	3265-3590
Cherty lime	3590-3635
Lime	3635-3691 TD

TOPS:

- 3114 - Heebner
- 3252 - Brn lime
- 3263 - Lansing KC
- 3512 - Penn. Cong.
- 3570 - Viola Chert
- 3614 - Simpson shale
- 3655 - Ordovician Cong.
- 3683 - Arbuckle

STATE

*S. A. Murphy*  
S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this 23rd day of March, 1953.

*Mrs. Gauthier*  
Notary Public

My commission expires: Feb. 5, 1957

**PLUGGING**  
FILE SEC 22-21-12  
BOOK PAGE 56 LINE 25