

15.185.19539.0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 22 TWP. 21s RGE. 12w E/W  
 Location as in quarters or footage from lines:  
SE NW SE/4


Lease Owner Southern States Oil Co.  
 Lease Name Rose #6 Well No. \_\_\_\_\_  
 Office Address P. O. Box 1365, Great Bend, Ks. 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 10/29/82  
 Plugging completed 11/5/82  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	280'	none
				5 1/2"	3591'	2379'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged off bottom at 3310', ran 1 barrel sand & 5 sacks cement. Shot  
& worked pipe at 2837', 2719', & 2601'. Pulled 23 joints, Shot pipe  
at 1711' pulled 52 joints. Well plugged with 3 sacks hulls, 50 cement,  
25 gel, 1 hull, plug, 125 50/50 pos., 4%gel, 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 82



My Commission expires: \_\_\_\_\_

Irene Hoover  
 Notary Public  
 STATE CORPORATION COMMISSION

NOV 18 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

Case # 6

SE NW SE/4

ROCK # 1 G. Sec. 22-21-12 Stafford County, Kansas

Company - S. A. Murphy  
Contractor - Virginia Drilg Co Inc.  
Commenced - November 2, 1959  
Completed Rotary @ November 13, 1959  
Elevation - 1853 KB  
Total Depth - Rotary - 3595

8 5/8" rot at 280 w/ 225 oz con.  
@ 5 1/2" rot at 3591 w/125 oz con  
50 bbl. black magic

FORMATION	DEPTH
Clay-sand-gravel	0- 230
Sand-redbed	230- 280
Redbed	280- 610
Anhydrite	610- 652
Shale	652- 660
Shale-shells	660-1509
Lime-shale	1509-1620
Lime	1620-1960
Shale-lime	1960-2160
Shale-shells	2160-2510
Shale-lime	2510-3012
Lime	3012-3080
Lime-shale	3080-3510
Lime	3510-3750
Lime-shale	3750-3503
Cherty Cong.	3503-3525
Cherty lime	3525-3561
Lime	3561-3575 TD

TOPS:  
 610 - Anhydrite  
 3116 - Hobbs  
 3249 - Iron lime  
 3263 - Limestone  
 3503 - Cong. (cherty)  
 3532 - Simpson shale  
 3588 - Anhydrite

*[Handwritten signature]*

RECEIVED  
 STATE CORPORATION  
 OCT 08 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

Subscribed and sworn to before me, a Notary Public,  
 this 7th day of December, 1959.

*[Handwritten signature]*  
 Notary Public

My commission expires: 2-5-61