

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 22 TWP. 21s RGE. 12w E/W  
Location as in quarters or footage from lines:  
C of NW/4 NE/4 SE/4


Lease Owner Southern States Oil Co.  
Lease Name Rose #11 Well No. \_\_\_\_\_  
Office Address P.O. Box 1365, Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 11/6/82  
Plugging completed 11/10/82  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3661'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	311'	none
				5 1/2"	3570'	2084'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged bottom with sand at 3275' & ran 5 sacks cement. Shot & worked pipe at 2547', 2435', 2327', 2215', & 2104'. Worked pipe loose at 2104'. Got 68 joints total. Plugged well with 3 sacks hulls, 50 sacks cement, 25 gel, 1 hull, 8 5/8 plug, 125 sacks 50/50 pos. 4% gel, 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1982

My Commission expires:



[Signature]  
STATE CORPORATION COMMISSION

NOV 18 1982

CONSERVATION DIVISION  
Wichita, Kansas

Rose #2 OWWO

Well: Rose #2 OWWO  
 Location: C NW/4 NE/4 SE/4 Section 22-21S-12W, Stafford County, Kansas  
 Company: S. A. Murphy Drilling Company, Inc.  
 Contractor: Virginia Drilling Company, Inc.  
 Commenced: November 13, 1947  
 Completed: November 26, 1947  
 Total Depth: 3661  
 Elevation: 1849

FORMATION	DEPTH	TOPS:	
Sand & Shells	0 - 255	Lansing	3254
Shale	255 - 290	Cherty Conglomerate	3524
Sand	290 - 311	Viola Chert	3630
Red Beds	311 - 495	Simpson Shale	3658
Red Bed & Shale	495 - 825		
Shale & Shells	825 - 1140		
Salt & Shells	1140 - 1430		
Shale & Shells	1430 - 1475		
Shale & Lime	1475 - 1595		
Lime	1595 - 1710		
Lime, hard	1710 - 1840		
Lime	1840 - 1960		
Lime & Shale	1960 - 2100		
Broken Lime	2100 - 2250		
Lime & Shale	2250 - 2355		
Shale	2355 - 2650		
Shale & Lime	2650 - 2760		
Broken Lime	2760 - 2845T-		
T-Lime	2845 - 2905		
Lime	2905 - 3125		
Lime & Shale	3125 - 3200		
Shale	3200 - 3246		
B. Lime	3246 - 3255		
Light Lime	3255 - 3273		
Lime	3273 - 3333		
Lime	3333 - 3498		
Shale	<del>3498 - 3635</del> = 3498 - 3575 = Shale		
Lime & Shale	3635 - 3661 X		

CIRCULATE:  
 1 hr @ 3333  
 1 1/2 hr @ 3345  
 1 3/4 hr @ 3381  
 1 1/2 hr @ 3426  
 1 1/2 hr @ 3635  
 1 1/2 hr @ 3661

Set 8 5/8" casing @ 311'

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 08 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and known of his own knowledge that the Rose #2 located in the C NW/4 NE/4 SE/4 Section 22-21S-12W, Stafford County, Kansas, was drilled to a total depth of 3661 feet. Same was plugged and abandoned.

*S. A. Murphy*  
*Notary Public*

Subscribed and sworn to before me, a Notary Public, this 28<sup>th</sup> of September 1947.

*Walter Stanton*

My commission expires February 5, 1949.