


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 22 Twp. 21 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Circle Oil Co., Inc.  
Lease Name Hewitt Well No. 2  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 21, 1966  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 21, 1966  
Plugging completed November 21, 1966  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (A. Elving)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	277	8-5/8"	1/13/66	
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 250 feet; Hull Plug and 25 sacks cement thru the drill pipe; Heavy Mud to 40 feet; Solid Bridged Plug and 10 sacks cement to base of cellar; 2 sacks in rat hole. Job completed @ 5:30 A.M.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 27 1966  
1-27-66  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1966

My commission expires November 26, 1966

Louise K. Whitted  
Notary Public

DRILLERS LOGHEWITT NO. 2

CASING RECORD:	COMPANY:	CIRCLE OIL CO.	DESCRIPTION:
8-5/8" @ 277' w/240 sax cement	CONTRACTOR:	SAGE DRILLING CO.	SW SW NW Sec. 22-21S-12W Stafford County, Kansas
TOTAL DEPTH:	COMMENCED:	January 13, 1966	ELEVATION: 1853 KB
3715'	COMPLETED:	January 21, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	395	
Shale & Red Bed	395	640	
Anhydrite	640	660	
Shale, Red Bed & Lime	660	1495	
Sandy Lime & Shale	1495	1875	
Lime & Shale	1875	2604	
Shale & Lime	2604	2830	
Lime & Shale	2830	3200	
Shale	3200	3247	
Lime & Shale	3247	3415	
Lime	3415	3475	
Lime & Shale	3475	3525	
Lime	3525	3609	
Lime & Shale	3609	3715	


**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JAN 27 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 24th day of January, 1966.

  
 Louise K. Whitted - Notary Public

My commission expires November 26, 1966