


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 11 Twp. 21S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Bennett Well No. 2
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed July 11, 1962 19
Application for plugging filed March 1, 1963 19
Application for plugging approved March 4, 1963 19
Plugging commenced March 12, 1963 19
Plugging completed March 18, 1963 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production November 4 1962
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus
Producing formation Arbuckle Depth to top 3529 Bottom _____ Total Depth of Well 3593 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225'	Cemented
				5 1/2"	3532'	2457'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 4 sacks of cement from 3545 feet to 3520 feet
Mudded from 3520 feet to 225 feet, rock bridge from
225 feet to 215 feet, ran 20 sacks of cement from 215
feet to 155 feet, mudded from 155 feet to 35 feet,
rock and 10 sacks of cement from 35 feet to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 19 63

My commission expires August 10, 1965

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: June 7, 1962

Contractor: Quaker Drilling Co., Inc.

Completed: June 15, 1962

Bennett No. 2
SE NW NE Sec. 11-21S-13W
Stafford County, Kansas

Elevation: 1872 K.B.

Casing Record

Set 8 5/8 Inch casing at 225 feet with 250 sacks cement
Set 5 1/2 inch casing at 3532 feet with 100 sacks cement


(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	175	Heebner	3129 -1257
Shale	225	Brown Lime	3256 -1384
Sand and Red Bed	435	Lansing	3268 -1396
Red Bed	713	Base of Kansas City	3494 -1622
Anhydrite	730	Conglomerate	3515 -1641
Shale and Shells	1545	Arbuckle	3529 -1657
Shale and Lime	1890	Rotary Total Depth	3545 -1673
Sandy Lime and Shale	2045		
Shale and Shells	2270		
Shale	2485		
Shale and Lime	2900		
Lime	3000		
Lime and Shale	3310		
Lime	3465		
Lime and Shale	3535		
Dolomite	3545		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE NW NE of Section 11, Township 21 South, Range 13 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By:


 Thomas M. McCaul

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC THIS 20th day of June, 1962


 Virginia Mundell, Notary Public
MY COMMISSION EXPIRES:
August 10, 1965

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: June 7, 1962

Contractor: Quaker Drilling Co., Inc.

Completed: June 15, 1962

Bennett No. 2
SE NW NE Sec. 11-21S-13W
Stafford County, Kansas

Elevation: 1872 K.B.

Casing Record

Set 8 5/8 Inch casing at 225 feet with 250 sacks cement
Set 5 1/2 inch casing at 3532 feet with 100 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	175	Heebner	3129 -1257
Shale	225	Brown Lime	3256 -1384
Sand and Red Bed	435	Lansing	3268 -1396
Red Bed	713	Base of Kansas City	3494 -1622
Anhydrite	730	Conglomerate	3515 -1641
Shale and Shells	1545	Arbuckle	3529 -1657
Shale and Lime	1890	Rotary Total Depth	3545 -1673
Sandy Lime and Shale	2045		
Shale and Shells	2270		
Shale	2485		
Shale and Lime	2900		
Lime	3000		
Lime and Shale	3310		
Lime	3465		
Lime and Shale	3535		
Dolomite	3545		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE NW NE of Section 11, Township 21 South, Range 13 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: *Dwight J. Wilson*
XXXXXXXXXXXXXXXXXXXX Dwight J. Wilson

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC THIS 20th day of June, 1962

Virginia Mundell
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1965

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas