


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 11 Twp. 21 Rge. (E) 13 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW SE
Lease Owner Westgate-Greenland Oil Company and Mallard Drilling Co
Lease Name Alphin - B Well No. 1
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 17, 1949 19
Application for plugging filed May 27, 1949 19
Application for plugging approved May 27, 1949 19
Plugging commenced July 16, 1949 19
Plugging completed July 26, 1949 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	282	8 5/8"	282	none
		0	3566	5 1/2"	3566	2499 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 3548 feet
Run 5 sacks cement from 3548 to 3510 feet
Filled with heavy mud 3510 feet to 280 feet
Run 15 sacks cement from 280 feet to 240 feet
Filled with heavy mud from 240 feet to 30 feet
Capped with 10 sacks cement from 30 feet to cellar base

RECORDED

AUG 1 - 1949 8-1-1949

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Don Allen (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Allen
1022 Union National Bank Bldg, Wichita 2, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of August, 1949.

Esther Russell
Notary Public.

My commission expires May 25, 1953

PLUGGING
FILE SEC 11 T 21 R 13a
BOOK PAGE 94 LINE 7

COMPANY: Westgate-Greenland Oil Company
 Mallard Drilling Company

CONTRACTOR: Mallard Drilling Company

FARM: Alphin B 1

LOCATION: SW NW SE Section 11-21-13W
 Stafford County, Kansas

COMMENCED: April 17, 1949--Rotary
 April 4, 1949--Cardwell

COMPLETED: April 26, 1949--Rotary
 May 17, 1949--Cardwell

0	to	235	Surface sand.
235	to	250	Shale
250	to	282	Red bed
282	to	775	Red bed
775	to	1300	Shale and shells
1300	to	1605	Shale and lime
1605	to	1740	Lime
1740	to	1950	Lime and sand
1950	to	2085	Lime
2085	to	2645	Shale and lime
2645	to	2755	Shale and lime
2755	to	2870	Lime
2870	to	3005	Lime and shale
3005	to	3085	Lime
3085	to	3185	Lime
3185	to	3288	Lime and shale
3288	to	3315	Lime
3315	to	3520	Lime
3520	to	3566	Arbuckle--T.D. Rotary
3566	to	3570	Arbuckle
		3570	T.D. --Cardwell

RECEIVED
 Conservation Div.
 MAY 27 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

Set 282 feet of 8 5/8" surface pipe. Cemented with 170 sacks cement.

Set 5" pipe at 3566. Cemented with 60 sacks cement.

TOPS: Arbuckle--3546 Kansas City--3266

Measurements taken from derrick floor.

Acidized with 1000 gallons from 3566 to 3570; show of oil and water. Plugged off from 3563 to 3570, and shot 36 holes from 3548 to 3558, and acidized with 1000 gallons water.

DRY

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Alphin B 1, Section 11-21-13W, Stafford County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 18th day of May 1949.

Harold Wright

My commission expires 12/4/52

PLUGGING
 FILE SEC. 11-21-13W
 CORR PAGE 99 LINE 7