

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Make or Have Report by
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plat

Stafford County, Sec. 11 Twp. 21 Rge. 13 (EQ W (W))
 Location as "NE/CNW/SE/SW" or footage from lines 75' W of NE SE NW
 Lease Owner Isern - Wells
 Lease Name SIPES Well No. 1
 Office Address Box 486 - Ellinwood, Ks. 67526
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed May 9th 1974
 Application for plugging filed May 9th 1974
 Application for plugging approved May 9 1974
 Plugging commenced May 9 1974
 Plugging completed May 9 1974
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Bieberstein
 Producing formation Depth to top Bottom Total Depth of Well 3575 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud.
 Bottom plug set at 500' with 40 sacks cement thru drill pipe
 Middle plug set at 250' with 25 sacks cement thru drill pipe
 Top plug set at 40' with 1/2 sk. hulls and 15 sacks cement
 2 sks. cement in rat hole

STATE RECEIVED
 STATE CORPORATION COMMISSION
 MAY 13 1974
 CONSERVATION DIVISION
 Wichita, Kansas
 5-13-74

Name of Plugging Contractor, Duke Drilling Co.
 Address, Box 823 - Great Bend, Ks. 67530

STATE OF Kansas, COUNTY OF Barton ss.
 Leonard Williamson employee of

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
 Box 823 - Great Bend, Ks. 67530

Subscribed and Sworn to before me this 10 day of May 1974

Notary Public, (Address) 4-11-78

DRILLERS' WELL LOG

DATE COMMENCED: May 1, 1974
 DATE COMPLETED: May 9, 1974

Isom - Wells
 S1P12 #1
 75' West of NE SE NW
 Sec. 11-T21S-R19W
 Stafford County, Kansas

ELEVATION: 1873 K.B.

0 - 15'	Surface Clay
15 - 125'	Sand
125 - 190'	Shale
190 - 240'	Sand
240 - 709'	Red Bed
709 - 731'	Anhydrite
731 - 1540'	Shale & Shells
1540 - 3124'	Lime & Shale
3124 - 3129'	Shale
3129 - 3152'	Lime & Shale
3152 - 3168'	Lime
3168 - 3252'	Shale
3252 - 3267'	Lime & Shale
3267 - 3400'	Lime
3400 - 3522'	Lime-Shale-Chert
3522 - 3575'	Dolomite

FORMATION TOPS

ANHYDRITE	709
HEWNER	3124
TORONTO	3152
DOUGLAS	3168
BROWN LIME	3252
KANSAS CITY	3267
BASE K.C.	3400
ARMUCKLE	3522
RED	3575

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 13 1974
 CONSERVATION DIVISION
 Wichita, Kansas
 AFFIDAVIT

SURFACE PIPE: Set used 8-5/8"
 20# at 300' with 225 sacks
 common cement, 2% Gel, 3% cc.

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 10 day of May 1974.

My Comm. Expires: April 11, 1978

Robert M. Hague
 Notary Public