


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 11 Twp. 21 Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner L. D. Davis
Lease Name McDonald Well No. 1
Office Address Box 324, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1974
Application for plugging filed March 1 1974
Application for plugging approved 1974
Plugging commenced March 14 1974
Plugging completed March 22 1974
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 1974
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	FULLED OUT
		0	289'	8 5/8"	289'	none
			3520 1/2'	5 1/2"	3520 1/2'	2518.30

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3240' and dumped 5 sacks of cement.

Halliburton plugged well pumping in 2 sacks of hulls, 10 sacks of gel and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

Subscribed and sworn to before me this 27 day of March 1974

My commission expires Feb. 10, 1975

George A. Meyer
Notary Public


15.185.01247.0000

Company - ATLANTIC REFG. CO.
Farm - McDonald No. 1

SEC. 11 T. 21 R. 13W
NE S1 SW

Total Depth. 3532'
Comm. 7-1-48 Comp. 7-25-48
Shot or Treated. Acidized w/1000 gals.
Contractor. Goodpaster Drlg. Co.
Issued. 10-2-48

County. Stafford
KANSAS



Elevation. 1872'

Production. 509 BOPD. Daily
allowable 32 BOPD

CASING:
8-5/8" 289' Cem. w/175 Sx.
5-1/2" 3520 1/2' Cem. W/150 Sx. (D.F.)

Figures Indicate Bottom of Formations.

surface soil & sand	95
iron pyrite	110
shale	200
sand	230
shale & shells	293
shale & shells & red bed	800
shale & shells	1375
salt, shale & shells	1675
shale & lime	1771
lime	1850
shale	1955
shale & lime	2150
shale & shells	2400
shale	2530
shale & shells	2645
shale & lime	2662
shale & shells	2810
shale & lime	3341
lime	3532
Total Depth	

Tops:	
Lansing	3272
Conglomerate	3500
Simpson	3510
Arbuckle	3520

Producing Area: 3520 1/2' to 3532'

DST 3350-3355 Open 45 mins.
Rec. 35' muddy wtr.
Drilled out cem. to T.D..
Filled up 200' oil in 30 mins.
Acidized w/1000 gals. down casing
mix. press. 600#. 2560' fillup
in 10 hours.
On 7 hr test swabbing from bottom
swabbed 31 BOPH, no water.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1974
CONSERVATION DIVISION
Wichita, Kansas