

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,500.00.00

LEASE NAME SCHMEIDLER C

WELL NUMBER 1

SPOT LOCATION NW NE NW

SEC. 10 TWP. 13S RGE. 16E (W)

COUNTY ELLIS

Date Well Completed 8-31-87

Plugging Commenced 11-23-87

Plugging Completed 11-24-87

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH, HAYS KS 67601

PHONE # (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS GILBERT SCHECK

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation ARBUCKLE & KC Depth to top _____ bottom _____ T.D. 3475

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>SURFACE</u>		<u>SURF</u>	<u>200</u>	<u>8 5/8"</u>	<u>200</u>	<u>NONE</u>
<u>PRODUCTION</u>		<u>SURF</u>	<u>3473</u>	<u>4 1/2"</u>	<u>3473</u>	<u>2700'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. DUMPED SAND DOWN WELL TO 3125' AND SPOTTED 4 SACKS OF CEMENT ON TOP OF SAND. SHOT OFF CASING AT 2700' AND PULLED. MIXED 150 SX THIRTY CEMENT WITH 500#'s HULLS AND PUMPED DOWN 8 5/8" CASING. SHUT IN PRESSURE 700#'s.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION

License No. 5128

Address 207 W 12TH, HAYS KS 67601

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS

COUNTY OF ELLIS

ss. DEC 7 1987

12-1-1987


R P NIXON

(employee of operator) Wichita, Kansas

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R Nixon

(Address) 207 W 12TH, HAYS KS 67601



SUBSCRIBED AND SWORN TO before me this 25 day of NOVEMBER, 1987

Lorna M Herrman
Notary Public
Lorna M Herrman

My Commission expires: 6-19-88