

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 10 Twp. 14 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW

Lease Owner Okmar Oil Company
Lease Sander "C" Well No. 1
Office Address 820 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-16-61 19____
Application for plugging filed 9-16-61 19____
Application for plugging approved 9-16-61 19____
Plugging commenced 9-16-61 19____
Plugging completed 9-16-61 19____
Reason for abandonment of well or producing formation Dry Hole

NORTH

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3580 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	175'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 540' with 20 sacks of cement
2nd Plug @ 175' with 20 sacks of cement
Top Plug @ 40' with 1/2 sack of hulls and 10 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Byron Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Byron Johnson
Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 1961

My commission expires April 1, 1963
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Okmar Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: Sander "C" #1
 LOCATION: NE NW NW Sec. 10-14-17
 ELLIS COUNTY, KANSAS
 COMMENCED: 9-8-61
 COMPLETED: 9-16-61

0	40	Top Soil & Sand
40	175	Shale & Shells
175	660	Shale & Sand
660	850	Sand
850	1199	Red Bed & Shale
1199	1237	Anhydrite
1237	1580	Shale & Shells
1580	1890	Shale & Lime
1890	2010	Lime
2010	2495	Lime & Shale
2495	2705	Shale & Lime
2705	3145	Lime & Shale
3145	3500	Lime
3500	3532	Lime & Shale
3532	3580	Arbuckle
	<u>3580</u>	<u>Rotary Total Depth - D. & A.</u>

Set 8 5/8" surface casing @ 175' with 125 sacks Sunset cement.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sander "C" #1, located NE NW NW of Section 10, Township 14, Range 17, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

Byron Johnson
RECEIVED Byron Johnson
 STATE CORPORATION COMMISSION

SEP 21 1961

STATE OF KANSAS)
) SS CONSERVATION DIVISION
 COUNTY OF BARTON) Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 19th day of September, 1961.

Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1963