

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-01,693-00
 01

LEASE NAME #2 Domico

WELL NUMBER _____

SPOT LOCATION SE NE SW/4

SEC. 21 TWP. 14 RGE. 16 (R) or (W)

COUNTY Ellis

Date Well Completed _____

Plugging Commenced 5/9/84

Plugging Completed 5/15/84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR D. Oil Co. bought by Kelso Casing Pulling

ADDRESS P.O. Box 278, Victoria, Kansas 67671

PHONE # (____) _____ OPERATORS LICENSE NO. _____

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	989'	none
				4 1/2"	3453'	1899.55

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 4 sacks cement, sand to 3330', & 4 sacks cement. Shot pipe at 2775', 2610', 2500', 2300', 2100', & 1900'. Pulled 46 joints of 4 1/2". Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, plug, & 100 sacks 50/50 poz 6% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347, Chase, Ks. 67524

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. MAY 16 1984

R. Darrell Kelso (employee of operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature: R. Darrell Kelso)
 (Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1984



Irene Hoover
 Notary Public

My Commission expires: _____