


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County. Sec. 5 Twp. 14S Rge. (X) 19 (W)

Location as "NE/CNW%SW%" or footage from lines. NW SE NE
Lease Owner Lee Phillips Oil Co. and Graves Drilling Co., Inc.
Lease Name Werth Well No. 1
Office Address 1532 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 16, 19 65
Application for plugging filed June 16, 19 65
Application for plugging approved June 16, 19 65
Plugging commenced June 16, 19 65
Plugging completed June 16, 19 65
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mudded up with heavy mud to 540 feet. Followed by wooden plug, 1/4 sack hulls and placed 25 sacks cement onto hulls. Mudded up with heavy mud to 210 feet followed by wooden plug, 1/4 sack hulls and 20 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1965

6-30-1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
412 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of June, 19 65

My commission expires April 30, 1967

[Signature]
Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Lee Phillips Oil Co. and Graves Drilling Co., Inc. 1532 Wichita Plaza Wichita, Kansas DRILLING COMMENCED: June 10, 1965

CONTRACTOR: Graves Drilling Co., Inc. 412 Union Center Wichita, Kansas DRILLING COMPLETED: June 16, 1965

CASING RECORD: 7 Jts. 222' 8-5/8" cemented with 175 sacks. LOCATION: Werth No. 1 NW SE NE Section 5-14S-19W Ellis County, Kansas

0 - 223	Shale, rock & lime
223 - 860	Shale
860 - 1549	Shale, shells & red bed
1549 - 1570	Lime & shale
1570 - 1860	Shale with lime
1860 - 3519	Lime & shale
3519 - 3544	Shale & lime
3544 - 3563	Lime & shale
3563 - 3854	Lime
3854 - 3866	Conglomerate
3866 - 3900	Lime
3900	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

RECEIVED STATE CORPORATION COMMISSION

JUN 30 1965

By [Signature] President

CONSERVATION DIVISION Wichita, Kansas

STATE OF KANSAS)
BUTLER COUNTY)

SS:

Subscribed and sworn to before me, a Notary Public, this 29th day of June, 1965.

[Signature]
Betty Brandt Notary Public

My commission expires: April 30, 1967