

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 2 TWP. 14S RGE. 17W EXW  
Location as in quarters or footage from lines:  
C SE SE NW - 445' FSL; 470' FEL, NW/4


Lease Owner Lebsack Oil Production, Inc. et al  
Lease Name Braun B-4 Well No. B-4  
Office Address P. O. Box 489, Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed January 25, 1983  
Application for plugging filed January 24, 1983  
Plugging commenced 2:00 AM, January 25, 1983  
Plugging completed 3:30 AM, January 25, 1983  
Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well District 6

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Heavy mud to 3500' with 20 sacks; heavy mud to 1200' with 20 sacks;  
heavy mud to 500' with 80 sacks; heavy mud to 260' with 40 sacks;  
10 sacks and Bridge at 40' and 10 sacks in rathole.  
Plugged with 180 sacks 50/50 Foxmic, 6% gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY  
(Signature) [Signature]  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas  
(Address) 67579

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1983.



[Signature]  
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

JAN 31 1983

Wichita Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - 15-051-23,332:00-00 - - - - - BRAUN B-1  
Located: C SE SE NW, Section 2-14S-17W, Ellis County,  
Kansas

OWNER: Lebsack Oil Production, Inc., et al  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 18, 1983  
COMPLETED: January 25, 1983

TOTAL DEPTH: 3590'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 136 Clay, Shale	Ran 6 joints 8 5/8", 24# new casing. 240.35' pipe set at 253' K.B. Cemented with 150 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 9:00 PM, 1-18-83, by Halliburton.
136 - 203 Sand	
203 - 1152 Shale	
1152 - 1187 Anhydrite	
1187.- 3545 Lime and Shale	
3545 - 3590 Ahy Lime	Plugged.

Deviation Surveys: 1/4° at 1840'  
1 1/4° at 3367'  
1 1/2° at 3590'

JAN 31 1983

REGISTRATION DIVISION  
WICHITA, KANSAS