


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County. Sec. 14 Twp. 14S Rge. (E) 20(W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Rains & Williamson Oil Co.
Lease Name CERNEY "A" Well No. 1
Office Address 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11 19 65
Application for plugging filed August 11 19 65
Application for plugging approved August 11 19 65
Plugging commenced August 11 19 65
Plugging completed August 11 19 65
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3798 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211.45'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 540', spot with 20 sacks cement, mud back to 210', set plug and hulls and 20 sacks cement, mud back to 40', set solid bridge and capped with 10 sacks cement. Plug down 10:00 p.m. 8-11-65.

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1965
8-19-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson oil Company
Address 1425 Wichita Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains ~~owner or operator~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August 19 65

Shirley Keck
Shirley Keck
Notary Public.

My commission expires January 8, 1968

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co. & Kern Drilling Co., Inc.
 Cerney "A" #1
 SE SE NW Sec. 14-14S-20W
 Ellis County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
 COMMENCED: 8-2-65
 COMPLETED: 8-11-65

Remarks: Set 211' of 8-5/8" surface casing at 217' w/200 sx. GL3 Quick Set Cement.

Formations:

Soil-Clay-Shale	40'
Shale & Shells	217'
Shale	755'
Shale & Sand	880'
Sand	1105'
Shale & Redbed	1410'
Anhydrite	1455'
Shale	1990'
Lime & Shale	2080'
Shale & Lime	2420'
Lime & Shale	2705'
Shale	2740'
Shale & Lime	2910'
Lime	3045'
Lime & Shale	3170'
Lime	3798'
Rotary Total Depth (D & A)	3798'

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1965

CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains
 Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 13th day of August, 1965.

My Commission Expires:
 July 25, 1968

Judith Caughlin
 Judith Caughlin, Notary Public