

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

#			

Locate well correctly on above  
Section Plat

Ellis County. Sec. 14 Twp. 14 Rge. 20 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines. NE NW NW  
 Lease Owner Murfin Drilling Co.  
 Lease Name Carney Well No. 1  
 Office Address 617 Union Center Wichita  
 Character of Well (completed as Oil, Gas or Dry Hole) Oil  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed June 18, 1962  
 Application for plugging approved June 21, 1962  
 Plugging commenced June 21, 1962  
 Plugging completed June 27, 1962  
 Reason for abandonment of well or producing formation Oil depeleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	298'	None
				5 1/2	3824'	2517'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3840' to 3780'. Mixed and dumped 4 sx. from 3780' to 3748'. Pulled casing to 500'. Mixed and circulated 20 sx. gel mud. Mixed and pumped in 20 sx. cement from 500' to 440'. Pulled casing to 180'. Mixed and pumped in 20 sx. cement from 180' to 120'. Pulled rest casing. Bailed off gel to 35'. Set 5' rock bridge from 35' to 30'. Mixed and dumped 10 sx. cement from 30' to base cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1962

CONSERVATION DIVISION  
Wichita, Kansas

7-16-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Acè Pipe Pulling Co.  
 Address Box 304 Great Bend, Ks.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Fred Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
617 Union Center, Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 62

My commission expires 12/18/65

[Signature]  
 Notary Public.



