



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

DEC 20 1965

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rain & Millerson has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rain & Millerson

Complete Address: 1425 Wichita Plaza

Lease Name: Rohr Well No. 91

Location: Se Se Ne Sec. 11 Twp. 15 Rge. 70(E) (W)

County Ellis Total Depth 3665 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Walker was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at ft. 540 ft., and displace 20 sac cement thru drill pipe, heavy mud to 240 ft., set cementing plug and displace 20 sac cement, heavy mud to 40 ft., set plug  $\frac{1}{2}$  sac hulls and 20 sac cement, cementing to base of cellab.

Very truly yours, Gilbert P. Leiker

Gilbert P. Leiker  
Conservation Division Agent