

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rowe of Slawson Drlg. has this
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Seeyle "B" Well No. 3

Location: NW SE SW Sec 35 Twp. 15 Rge. 19 (E)(W)X

County: Ellis Total Depth 3304 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace

30 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION
Very truly yours,
JUL 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Leo F. Massey
Conservation Division Agent