

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lawell Moore of C & Y Drilling Co. has this  
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen

Complete Address: Logan Kansas

Lease Name: Leiker Well No. 1

Location: N<sup>1</sup>/<sub>2</sub> - NW - NW Sec. 19 Twp. 15 Rge. 17 (E) (W)

County Ellis Total Depth 3633 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Moore was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 570 ft  
and displaced 25 sac cement thru drill pipe, heavy mud to 240 ft., set  
cementing plug and displaced 25 sac cement, heavy mud to 40 ft., set  
cementing plug, 1/2 sac hulls and 10 sac cement, cementing to base of cellar.

Very truly yours,

Gilbert P. Leiker

Conservation Division Agent