

State of Kansas



15.185.01421.0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

APR 19 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc. and Graves Drilling Co.

Complete Address: Box 332, ElDorado, Kansas

Lease Name: Curtis "E" Well No. # 1

Location: SW SE SE Sec. 31 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3646 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

304' of 8 5/8" surface pipe cement circulated. Fill hole to 290' with drilling mud, 1st cementing plug, 1/2 sack hulls, cement with 20 sacks. Fill hole to 40' with mud, 2nd cementing plug, 1/2 sack hulls, cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent