

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,706

LEASE NAME Fischer

WELL NUMBER #1

SPOT LOCATION SW NW NE

SEC 31 TWP 21 RGE 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 6-20-85

Plugging Completed 7-18-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Grady Bolding Corporation

ADDRESS Box 244, Great Bend, Ks. 67530

PHONE #(316)793-8628 OPERATORS LICENSE NO. 7383

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One. (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	294'	None
				5-1/2"	3680'	2,465.91'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3350' and 5 sacks cement. Shot casing at 3000', 2750', 2500' and 2050'. Pulled 62 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, released plug and pumped 150 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 700 psi and shutin 300 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 7-23-85

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

CONSERVATION DIVISION SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1985

My Commission expires: _____
Wichita, Kansas
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public